



Outdoor Lighting Concepts

9839 Northwest 20th Street | Coral Springs, Florida 33071
561-866-5896 | outdoorlightingconceptsfl@gmail.com | <https://outdoorlightingconcepts.com>

RECIPIENT:

Danielle Cucalon
21351 Whitaker Drive
Boca Raton, Florida 33433

Quote #1253	
Sent on	Sep 02, 2024
Total	\$103,190.00

Product/Service	Description	Qty.	Unit Price	Total
	Disconnect and remove existing 100A (12) Circuit 120/240 Single Phase street light load center due to corrosion.			
	Supply and install (1) new 125A (12) circuit Nema 3R load center. Install new stainless steel support rack with all new stainless steel hardware.			
	Supply and install (2) 5/8 x 8' copper ground rods with new #6 solid grounding electrode conductor.			
	Label and Install panel schedule upon completion.			
	Bore (1) new 1" underground conduit from new lighting service rack to each new light pole location on Valencia Dr.			
	Underground utility locates prior to underground conduit install.			
	Install (9) new 21' fiberglass poles on Valencia Dr.			
	Supply and install (1) new handhole at each new light pole location, install all new pea rock in handhole. Supply and install all new underground NSI splice kits as needed.			
	Supply and install all new wire from new 125A panel to each new light pole.			



Outdoor Lighting Concepts

9839 Northwest 20th Street | Coral Springs, Florida 33071
 561-866-5896 | outdoorlightingconceptsfl@gmail.com | <https://outdoorlightingconcepts.com>

Product/Service	Description	Qty.	Unit Price	Total
	Install (9) new LED post top fixture on each one of the new fiberglass poles.			
	Wire and test all new terminations upon completion.			
	Auger/ Water Truck/ Bucket Truck with Operator			
	Design and Engineering			
Items not Included	1. Repairs and or code upgrades to existing wiring and or equipment. 2.Any unforeseen wiring issues at time trouble shooting and or times of new work installation 3.All modifications and or changes to the original scope must be approved prior to start of ANY work 4. Sod and or landscape restorations. 5.Asphalt and or concrete restorations. 6.Permit Fees 7.FPL feeders 8.FPL fees			
Total Included		1	\$88,700.00	\$88,700.00
21' Fiberglass DB Pole		9	\$1,399.00	\$12,591.00
				Optional
Modern Street Light 80 - 150 Watt 9 Beam Spreads 2700k,3000k or 5000k Color		1	\$1,899.00	\$1,899.00
				Not included
Boca Grove To Supply Fixture From Inventory		1	\$0.00	\$0.00



Outdoor Lighting Concepts

9839 Northwest 20th Street | Coral Springs, Florida 33071

561-866-5896 | outdoorlightingconceptsfl@gmail.com | <https://outdoorlightingconcepts.com>

This quote is valid for the next 30 days, after which values may be subject to change.

Total

\$103,190.00